


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS  
Farm- Brack No. 1

SEC. 17 T. 15 R. 12W  
NE NW NE

Total Depth. 3313'  
Comm. 9-28-59 Comp. 10-6-59  
Shot or Treated.  
Contractor.  
Issued. 11-28-59

County Russell  
KANSAS



Elevation. 1840' DF

CASING:

8 5/8" 359' cem w/150 sx.

Production. Dry

Figures Indicate Bottom of Formations.

shale & pest rock	55
sand & gravel	65
shale	200
shale & hard sand	250
shale	320
shale & shells	490
red bed	760
Anhydrite	792
shale & shells	1450
shale & lime	2885
lime	2933
lime & shale	3025
lime	3313 RTD
Total Depth	

TOPS:

Anhydrite	760
Topeka	2680
Heebner	2913
Toronto	2931
Douglas	2946
Brown Lime	2999
Lansing	3016
Base Kansas City	3241
Conglomerate	3273
Arbuckle	3306

DST #1 3180-3200, op 1 hr., w/a weak, steady  
blow thruout the test; rec. 105' of gas  
cut watery mud. IFP 100#, FFP 120#,  
BHP 890#/20 min.

DST #2 3307-13', op 1 hr w/a very strong  
blow thruout test; rec. 1800' salt water.  
IFP 185#, FFP 800#, BHP 1075#/20 min.