


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SHIELDS OIL PRODUCERS
Farm. F. E. Parker No. 1

SEC. 18 T. 15 R. 12W
NW NE SW

Total Depth. 3304
Comm. 3-29-53 Comp. 5-1-53
Shot or Treated.
Contractor. Shields Drilling Co.
Issued. 6-13-53

County Russell
KANSAS



CASING:
13 3/8 420' 7 in. 3008'
10 in. 800'
8 in. 2067'

Elevation. 1836 DF

Production. Dry

Figures Indicate Bottom of Formations.

cellar	8	red rock	2035	lime	3275
post rock	18	3 1/2 BW 2045-55		conglomerate	3279
shale	150	lime	2085	Arbuckle lime	3304
sandy	170	shale	2090	HFV	
red rock	175	lime	2120	Total Depth	
shale	205	shale	2125		
sandy	215	red rock	2130	TOPS:	
water sand	225	lime	2135	Tarkio	2350
red rock	245	shale & shells	2220	Heebner	2919
sand	270	shale	2225	Dodge	2940
shale	290	lime	2250	Lansing KC	3002
red rock	320	shale	2260	Conglomerate	3275
shale	420	lime shells	2342	Arbuckle	3279
sand HFV	425	lime	2352		
shale	435	red rock	2358		
sand	445	shale	2415		
shale	455	lime	2450		
iron	460	shale	2470		
shale	470	lime	2485		
red rock	772	shale	2490		
anhydrite lime	800	lime	2500		
red rock	815	shale	2505		
shale	845	lime	2515		
red rock	985	lime shells	2540		
shale	1040	shale	2543		
red rock	1080	lime	2565		
shale & lime shells	1195	shale	2615		
lime	1200	lime	2630		
salt	1430	shale	2650		
shale & shells	1455	lime	2670		
shale	1460	shale	2680		
lime	1475	lime	2770		
shale	1480	shale	2780		
lime	1495	lime	2930		
shale	1515	shale	2940		
lime	1545	lime S O & G	2955		
shale	1550	red rock	2960		
lime	1565	shale	3002I		
shale	1570	Lansing lime	3010		
lime	1660	V S S O			
shale	1670	shale	3017		
lime	1675	KC lime S S O	3080		
red rock	1690	shale	3084		
1 BW 1755-65		lime	3112		
lime	1825	shale	3115		
red rock	1830	lime	3165		
lime	1865	3 BWPH @ 3165			
shale	1870	shale	3170		
lime	1895	lime	3180		
shale	1910	shale	3185		
red rock	1915	lime	3210		
lime	1955	shale	3220		
shale	1965	lime	3240		
red rock	1980	shale	3245		
lime	2000	lime	3260		
shale	2005	shale	3269		
lime	2020	red rock	3270		