

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - SHELLEY OIL COMPANY
Farm - Parker "B" No. 1

SEC. 18 T. 15 R. 12W
NE 1/4 DE
330' fr ML & 330' fr WL W 1/2
of the SE 1/4
County. Russell

KANSAS



Total Depth. 3328'
Comm. 11-11-48 Comp. 11-25-48
Shot or Treated.
Contractor. Claude Wentworth Drlg. Co.
Issued. 12-25-48

CASING:
8-5/8" 700' Cen. W/75 Sx.
OD casing set 6' in cellar

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface soil, lime	
& shale	65
clay & shells	150
sand	185
sand & pyrites of	
iron	205
clay, shale & shells	430
red bed & shells	772
anhydrite	730
anhydrite	820
shale & shells	1025
shale & salt	1190
salt	1340
shale & lime	1505
lime brkn & shale	1650
lime & shale	3260
wh xlyn lime	3293
conglomerate	3307
fine to coarsely xlyn	
dolomite	3328
Total Depth	

Tops:

Anhydrite	772
McBner Shale	2925
Lansing Lime	3012
Conglomerate	3293
Arbuckle Lime	3307

Fair por. , no shows 3328'

Since no commercial oil or gas
prod. was encountered in drlg.
to 3328', regular authority was
granted to plug the well & abandon
the location.

Plugged as follows:
11-28-48, 28 sx cem. 3328' to 3258'
Mud laden fluid 3258' to 970'
25 sx. of cement 970' to 700'
Shot 8-5/8" OD casg. at 479'

Parted 8-5/8" casg & pulled 18' of
8-5/8" OD, 28.55, 8R thd., welded
line casing.

Mud laden fluid 700' to 200'
20 sx. of cement 200' to 140'
Mud laden fluid 140' to 40'
20 sx. of cement 40' to 6'
surface soil 6' to 0'

Plugged & abandoned Nov. 30, 1948