

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


DEEPENING RECORD:

Company - SOHIO PETROLEUM CO.
Farm - Meier No. 2

SEC. 20 T. 15 R. 12W
CN₂ SW SE

Total Depth. 3559
Comm. 10-29-46 Comp. 11-22-46
Shot or Treated.
Contractor. Biddle Drlg. Co.
Issued. 4-23-49

County. Russell
KANSAS



CASING:
8-5/8" 316' Cem. W/150 Sx.
5" 3353'

Elevation. _____

Production. S.W.D.W.

Figures Indicate Bottom of Formations.

post rock & shale	50
shale & shells	105
sand & shale	265
red bed & shale	319
T.D. WDC 319'	
red bed & shale	625
red rock	700
sand hrd	735
shale blue	770
shale & pyrite iron	795
anhydrite	835
red rock & shale	1030
red bed & shale	1255
salt & lime	1425
salt & shale	1475
shale	1510
shale & lime	1570
lime & shale brkn	1645
shale & lime	2755
lime	2885
lime & shale	2970
lime & shale brkn	3030
lime & shale	3085
lime & shale brkn	3140
lime & shale	3195
lime & shale brkn	3276
lime & shale	3314
lime hrd	3340
lime	3348
lay down drill pipe & draining up.	
lime & shale	3390
lime	3404
Total Depth	

Tops:
Conglomerate 3308
Arbuckle 3338

DEEPENING RECORD:

Deepened by: Sohio Petro. Co.
Commenced 12-15-48
Completed 12-22-48
Total Depth: 3559'
Production: S.W.D.W.

Well originally comp. 11-22-46
Arbuckle 3338 - 1485
5" - 3353
8-5/8" - 316 W/150 Sx.
Commenced 12-16-47
Completed 12-17-47
O.W.D.D. for SWDN
New: DD 3451' TD. Took 165 BWPH
by gravity.
12-15-48 - OWDD * New Drilling 3537'
12-22-48 - Gran. 3557-59 Total Depth
Acidized W/5000 gals.
Took 320 BWPH on vac.