

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


24-15-13W

Company - NADEL & GUSSMAN
Farm - Luerman No. 1.

SEC. 24 T. 15 R. 13 W
SEc NE

Total Depth. 3344'
Comm. 12-19-43 Comp. 1-17-44
Shot or Treated.
Contractor. Thos.H.Allan
Issued. 1-29-44

County. Russell
KANSAS



CASING:
8 5/8" 216' Cem.
5 1/2" 3323' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale blue	0-150
Dakota sand & shale	450
red beds	804
anhydrite white	830
red beds	1100
shale & salt	1500
shale & shells	1750
lime	1850
shale & shells	2725
lime	2985
shale	3030
lime	3069
lime porous, poor saturation, no odor, probably wtr	3077
lime	3112
lime porous, no odor (wtr)	3142
lime	3225
shale & lime	3285
lime buff crystalline	3310
shale varicolored	3319
conglomerate cherty	3321
dolomite-partly porous & oil saturated	3325
T.D. rotary table meas.	3327
5 1/2" csg cemented	3323
changed to cable tools	
dolomite & cave-test 3 gal. wtr & little oil	3328
dolomite-treated w/50 gal. acid-test same	3329
dolomite	3338
shale red	3341
dolomite, wtr, 50' per hr	3344
Total Depth.	

Formation Tops below Floor:

Anhydrite	804
Topeka	2725
Lansing	3030
Conglomerate	3319
Arbuckle	3321
Water	3343