

26-15-13W


SIGNAL OIL COMPANY,
 Taylor No. 2.

SEC. 26 T. 15 R. 13W
 Center E.L. SE $\frac{1}{4}$

NOV 17 1934

County. Russell.

Total Depth. 3387' P.B. 3142
 Comm. 7-25-34 Comp. 11-6-34.
 Shot or Treated.
 Contractor. Braden-McClure Drilling Co.
 Issued, 11-17-34.



CASING.

133/8"	446'	65/8"	3064	
10"	845	312' of 5 1/2" liner set at 3368		Elevation.
8 1/4"	2125'			

Production. DRY

Figures Indicate Bottom of Formations.

clay and lime breaks	35	shale and shells	2595
shale	225	lime	2600
sdv shale	235	shale blue	2622
red rock	240	lime	2627
sand	250	shale blue	2655
shale	345	lime blue	2665
sand water	355	lime broken	2715
slate	370	lime	2835
sand	380	shale white	2838
slate	400	lime white	2970
sand	410	slate blue	2975
slate	430	lime	3000
sand	505	shale	3062
red rock	810	lime Oswald	3073
red rock	830	shale	3076
lime	860	lime	3267
slate white	875	shale blue	3280
red rock	885	lime broken	3325
shale blue	892	conglomerate	3363
red rock	1050	3363 equals 3368 cable meas.	
shale blue	1095	quartzite	3387
red rock	1150	Total Depth.	
slate	1250		
salt	1475		
shale	1500		
lime	1515		
lime and shale breaks	1660		
shale	1690		
lime broken	1710		
shale	1725		
red rock	1740		
lime broken	1955		
shale blue	1960		
lime white	1970		
red rock	1980		
lime white	2010		
red rock	2030		
lime broken	2075		
lime	2090		
red rock	2100		
lime broken	2120		
lime	2128		
lime broken	2175		
red rock	2180		
lime	2200		
shale grey	2218		
lime	2265		
shale	2280		
lime	2290		
shale grey	2315		
lime broken	2410		
shale blue	2425		
lime white	2445		
shale blue	2460		
lime	2490		
shale dark	2500		
lime white	2530		
shale white	2545		

SAND RECORD.

Oswald lime	3062-3325
conglomerate	3325-3368
Quartzite	3368-3387

WATER RECORD.

7 BWPHR	225-235
HFV	345-355
HFV	446-480
4 BWPHR	2110-2120
1/2 BWPHR	2525-2530
6 1/2 BWPHR	2990
1/2 BW	3115

OIL AND GAS RECORD.

show of oil and gas	2500
show of oil	2905
show of oil	2920
show of oil	3090
show of oil and gas	3115
20 bbls show	3368-3370

Plugged back from 3387 to 3142 and acidized produced some oil but mostly wtr. Abd.