


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

LEADER OIL CO.
W.H.Berrick No. 3.

SEC.6 T.15 R.13W
NEc NE

Total Depth. 2931'
Comm. 12-21-40 Comp. 1-11-41
Shot or Treated. 6000 Gals.
Contractor. Ruso Drlg.Co.
Issued. 3-22-41

County. Russell



CASING:
10 $\frac{3}{4}$ " 285' Cem.
7" 2916' Cem.

Elevation.

Production. Pot.1639 B. Phy.
no wtr

Figures Indicate Bottom of Formations.

sand, shale, red rock	95
shale & shells	500
shale & red bed	605
shale & shells	685
anhydrite	735
shale	885
shale & shells	1130
salt	1345
lime shells	1370
lime	1520
lime brkn	1690
lime	1900
shale	2060
lime	2170
shale	2215
lime	2260
shale	2415
lime	2630
lime hrd	2695
lime	2832
shale gy	2837
lime	2873
shale gy sdy	2900
lime wh	2904
shale gy	2908
lime	2931
Total Depth.	

Tops:

Dodge lime 2837
saturated core 2839-47
Kansas City 2908
light saturation 2910-11
oil 2918-31, hole filled
200' in 2 hrs, to 900'
in 24 hrs, acidized w/
6000 Gals.

Coring Record:

Core #1 2832-50 18' rec
2832-37 gy shale; 2837-39
lime gy; 2838-47 good sat;
2847-50 lime gy
Core #2 2873-91 15' 3" rec.
all gy sdy shale
Core #3 2900-18 18' rec
2900-04 wh lime; 2904-08
shale gy; 2908-18 lime gy;
light saturation 2910-11