

W.I. SOUTHERN, INC.
 W.H. Borrick No. 1.


SEC 6 T. 15 R. 13W.
 NW NE NE

Total Depth. 2926
 Comm. 1-8-36 Comp. 4-14-36
 Shot or Treated. 4000 gal acid.
 Contractor.
 Issued. 7-4-36

County. Russell.

CASING.

20"	20'	8 $\frac{1}{2}$ "	2835 SLM
15 $\frac{1}{2}$ "	240'	6"	2860'
133/8"	713'		
10"	2062'		



Elevation. 1747

Production. Pot. 848 B. in
 24 Hours.

Figures Indicate Bottom of Formations.

cellar	10	limo	2150
clay yellow	40	shale	2160
shale	80	limo	2175
red rock	105	shale	2180
Part iron	111	limo	2200
slate light	155	shale light	2210
red rock	165	limo	2220
slate	175	red rock	2225
shale grey	205	shale and shells	2260
sand	225	red rock	2265
HFW 205-10		shale and shells	2280
shale	245	shale	2310
water sand	270	limo	2350
HFW 245- 70		shale	2350
slate	280	sdv limo	2365
slate light	310	shale	2375
shale blue	340	limo	2430
red rock	697	shale	2435
chalk	702	limo	2460
limo	740	slate light	2475
red rock	905	limo	2485
slate blue	950	slate light	2500
red rock	1010	sdv shale	2515
shale blue	1110	limo	2540
salt	1350	shale	2545
shale	1370	limo hard	2575
limo	1425	shale	2580
shale light	1435	limo	2820
limo	1490	slate blue	2825
slate	1495	broken limo	2835
limo broken	1540	SLM 2842-2838	
small show gas 1530		limo	2852
limo	1760	show oil and gas 2835-38	
red rock	1770	slate	2860
limo	1925	broken limo	2868
shale	1930	Gas at 2962 est 4 Million	
limo	1970	Spraying oil 2869 from Topoka limo.	
red rock	1985	limo	2897
limo	2015	shale	2911
shale and shells	2030	Top Dodge 2911	
red rock	2045	limo	2926
limo	2055	increase in oil 2911-15	
shale blue	2060	B fore starting to acidize	
limo	2070	Acidized 4000 gal acid.	
shale	2075	pumped 503 bbls in 18 hours.	
limo	2085	Potential 848 bbls in 24 hrs.	
shale	2100	Total Dept .	
shells	2115		
limo	2125		
shale	2135		