

THE CARTER OIL CO.
D. Josephine No. 3.

SEC. 7 T. 15 R. 13W.
SE NE SE
990' fr N and 330' fr EL

Total Depth. 3231.
Comm. 6-29-37 Comp. 8-5-37
Shot or Treated. 1500 gal 3226-31
Contractor. Mac and Stauffer
Issued. 10-16-37

County Russell.



CASING. Rotary.

10 3/4" 413'
6" 3220'

Elevation. 1780

Production. Pot. 1704 B.

Figures Indicate Bottom of Formations.

surface	45
shale and shells	782
lime	822
broken lime	875
shale shells and red bed	972
shale and shells	980
shale	1097
lime	1198
shale and shells	1364
salt and shale	1405
shale and shells	1463
lime and shale	1576
lime	1667
broken lime and shale	1836
shale	1894
lime	2008
broken lime and shale	2025
shale	2085
lime	2218
shale	2290
lime and shale	2384
shale	2425
lime and shale	2558
lime	2715
lime hard	2756
lime	2845
shale	2860
lime	2913
lime and shale	2947
shale	2952
lime K.C.	2975
shale and lime	2993
lime K.C.	3016
lime	3115
shale	3120
lime	3219
shale	3221
lime	3231
Total Depth.	

2945
1780
-1165

3226
1780
-1446

Good show oil 2902-09 1/2
Top Douglas. 2915
Kansas City Lansing 2945
small show oil 2965-70
good show oil 2980-95
good show oil 3140-45
good show oil 3226-31

siliceous 3226-3231