

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE CARTER OIL CO.
D. Josephine No. 6


SEC. 7 T. 15 R. 13W
SEc SE
280' fr EL 335' fr SL SE $\frac{1}{4}$

Total Depth. 2974
Comm. 6-5-41 Comp. 6-20-41
Shot or Treated. 5000 Acid.
Contractor.
Issued. 8-23-41

County Russell.

CASING.

85/8" 214' cemented.
5 $\frac{1}{2}$ " 2933' cemented.



Elevation.

Production Pot. 1300 B.

Figures Indicate Bottom of Formations.

shale sand and anhyd.	222
anhydrite	240
red bed and sand	300
shale and pyrites	375
shale and shells	723
anhydrite	800
red bed, shale and shells	1015
shale and salt	1465
lime broken	1576
broken lime & shale	1735
shale	1780
lime	1810
broken lime and shale	1830
lime	1895
lime and shale	2000
lime	2040
lime and shale	2088
shale with lime streaks	2222
shale and shells	2435
shale	2590
lime & shale broken	2646
lime	2686
2686 equals 2680 S.L.Corr.	
shale and lime	2780
lime	2895
shale and limo	2940
lime	2974 (Std tools)
Total Depth.	

Tops	Topeka	2625
	Dodgo	2884
	K.C.limo	2927

show oil 2884-86
Good show oil 2964-74