

THE CARTER OIL CO.
J. Detrich No. 1.

DEEPENING RECORD.

SEC. 8 T. 15 R. 13W.
SWc SW
330' fr S. & W. lines
S $\frac{1}{2}$ S $\frac{1}{2}$

Total Depth. 3211
Comm. 11-9-36 Comp. 12-14-36
Shot or Treated. 3000 gal 2310-15
Contractor. Mac and Stauffer.
Issued. 2-26-38

County Russell.



Rotary 2743
CASING. Cable 2743-2888

12 $\frac{1}{2}$ " 320'
8 $\frac{1}{2}$ " 2737'
7" 2878'
6" 3207'

Elevation. 1779

Production. Pot. 210 B.

Figures Indicate Bottom of Formations.

surface	18
shells and lime	155
sand hard	235
sand	263
shells	275
lime shells	340
lime	350
limo blue	450
shale red	535
lime	550
shale blue	575
shale red	745
lime white	780
anhydrite	800
shale blk	868
shale blue	965
shale grey	1085
shale	1195
salt	1260
shale	1410
broken grey lime	1535
limo	1640
lime white	1750
limo	1835
lime grey	1890
lime	1945
lime grey	2037
shale	2085
lime grey	2147
limo	2193
shale	2230
lime	2463
lime grey	2548
lime	2615
shale	2630
lime	2740
cored lime	2742
cored Sat. lime	2743
limo	2758
lime	2810
Porous lime show oil & Gas	2815
limo	2865
shale	2878
lime	2888
Total Depth.	

DEEPENING RECORD.

Comm. 7-17-37
Comp. - 7-31-37
Prod. Pot. 1542 B.
1000 gal acid.
7" 2870

lime	2888-2896
shale	2904
red rock	2910
shale	2924
lime	2975
shale blue	2980
Total Depth.	
2 million gas	2950
Top 1st pau in K.C.	2962
Good show oil	2878-88
show oil	2962-75

Kansas City 2934-2980
Gas sand 2940-2950

DEEPENING RECORD.

Comm. 1-19-38 Comp. 1-24-38
Prod. Pot. 1750.56 B.
lime 2980- 3112
cored lime 3135
lime 3197 Top Arbuckle
cored lime 3207 3206
cored Arbuckle 3211
Total Depth.
show oil 3204-3210 $\frac{1}{2}$
good show oil 3210 $\frac{1}{2}$ -3211

Topoka lime	2830-2888
small show	2742-2743
small show	2790-2794
Big pay	2881-2888

2934
1779
1155