


THE CARTER OIL CO.
 J. Detrich No. 4.

SEC. 8 T. 15 R. 13W
 NW SW SW
 330 fr N & W Lines S $\frac{1}{2}$ S $\frac{1}{2}$

County. Russell

Total Depth. 3188'
 Comm. 4-15-37 Comp. 5-13-37
 Shot or Treated.
 Contractor. Mac & Stauffer
 Issued. 7-24-37 Rotary O-3183
 Cable 3183-88

CASING:
 12 $\frac{1}{2}$ " 407'
 7" 3183'



Elevation. 1759

Production. Pot. 1570 B.
 No wtr.

Figures Indicate Bottom of Formations.

soil		4
clay		15
shells, rock		40
shale, shells		100
shells		150
shells, shale blue		230
shells		280
lime, shells		457
shale		672
shale, shells		730
anhydrite lime		769
lime shale		915
shale shells		1165
salt		1405
shale shells		1505
brkn lime		1590
lime		1647
brkn lime		2496
lime		2768
cored lime		2788
very small show oil		
lime		2850
cored lime		2881
shale		2913
K.C. lime		2933
cored lime	5' sat.	2951
cored lime		2958
cored lime	saturation	2961
lime		2966
lime hrd		2980
lime sft		2991
lime hrd		3010
lime sft		3028
lime hrd		3105
shale		3113
lime hrd		3117
lime		3125
shale		3130
lime		3140
shale		3145
shale, lime		3160
cored shale, lime		3170
lime		3171
cored lime		3188
Total Depth.		

2913
 1759
 -1154

3183
 1759
 -1424

Siliceous 3183-3188
 Topeka 2610
 Kansas City 2913