

THE CARTER OIL CO.
J. Detrich No. 8.

SEC. 8 T. 15 R. 13W
NE SE SW

Total Depth. 3174'
Comm. 10-4-37 Comp. 10-20-37
Shot or Treated. 1500 Gals. 3168-3174
Contractor. Mac & Stauffer
Issued. 12-4-37 Rotary O-3174

County. Russell



Elevation. 1745

CASING:

10" 410'
6" 3168'

Production. Pot. 1944 B.
No wtr.

Figures Indicate Bottom of Formations.

soil	12
gravel	35
sand, rock	80
sand	120
sand, rock	172
sand, shale	360
shale, lime	418
red bed, sand	675
anhydrite, lime	730
lime	760
shale, lime shells	930
shale	1185
salt, shale	1225
salt	1380
lime	1560
shale	1630
lime	1878
lime, shale	1970
lime	2102
shale	2230
lime	2265
shale	2390
shale, lime	2425
lime	2485
shale	2520
brkn lime	2594
shale	2610
lime, shale	2652
lime	2770
lime, shale	2790
brkn lime	2825
lime	2840
cored lime	2853
lime	2865
shale	2895
lime	2920
cored lime	2948
lime	3089
cored lime	3104
cored shale	3107
lime	3156
shale, lime	3168
cored Siliceous lime	3174
Total Depth.	

Siliceous 3168-3174

Howard-Topoka 2540 - Top
sh oil 2847-52
Douglas 2860 - Top

Good Sh oil 2927-45
Kansas City lime 2908 - Top.
S.S.O. 3087-95

2908
1745

1163