

CARTER OIL COMPANY
J. Detrich No. 14 (twin #3)

SEC. 8 T. 15 R. 13W
SEC SW

Total Depth. 2947
Comm. 5-27-41 Comp. 6-13-41
Shot or Treated. 10,000 gal acid.
Contractor.
Issued. 9-6-41

County Russell.



CASING.

8 5/8" 223' cemented.
5 1/2" 2910' cemented.

Elevation.

Production. Pot. 625 B.

Figures Indicate Bottom of Formations.

clay and shale	35
shale sand&anhydrite	245
red rock	285
shale and pyrites	345
shale & shells	675
shale & red beds	975
shale and salt	1410
lime and sticky shale	1565
lime and shale	1825
lime broken	1870
shale and lime	2085
shale & broken lime	2190
shale & lime shells	2275
shale and shells	2378
lime and shale	2528
shale and shells	2560
lime	2604
lime broken	2622
lime	2657
lime & shale broken	2757
lime	2877
shale	2905
lime	2913
lime	2947
Total Depth.	

Top Topoka 2600
K.C. lime 2902

Fair porosity and saturation 2857-63
Good show oil 2932-46