


GULF OIL CORP.  
 George Rein No. 2.

SEC. 8 T.15 R.13W  
 CS  $\frac{1}{2}$  SE NE

Total Depth. 3343' PB 3070'  
 Comm. 3-8-40 Comp. 4-20-40  
 Shot or Treated. 4-19-40 4000 Gals. Acid  
 Contractor.  
 Issued. 7-27-40

County. Russell



CASING:  
 8 5/8" 476'  
 5 1/2" 3118'

Elevation.

Production. Pot. 255 B.  
 45 BW

Figures Indicate Bottom of Formations.

clay & shale	120
shale & shells	476
red rock	485
shale & shells	510
redrock	825
anhydrite	858
shale & shells	1195
salt & shells	1378
salt	1440
lime shells & shale	1480
lime brkn	1573
shale & lime	1609
lime & shells	1750
lime brkn	1767
lime	1943
lime & shells	1991
lime brkn	2015
lime	2047
lime brkn	2082
lime & shells	2179
lime brkn	2295
shale & shells	2344
shale	2440
shale & lime	2553
shale & shells	2692
shale & lime	2740
lime Topeka	2811
lime	2994
shale	3026
lime KC	3152
lime	3168
lime hrd	3188
shale	3200
lime brkn & shale	3243
lime	3300
shale	3319
conglomerate	3340
Arbuckle lime	3343
Total Depth.	

Plugged back 3070

Lansing-Kansas City lime 3026-70