

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.  
Rogg "D" No. 2.

SEC.9 T.15 R.13W  
CWL NE  
1320' N 330' E Cen.

Total Depth. 3321=3322  
Comm. 11-25-40 Comp. 12-7-40  
Shot or Treated. 5000 Gals.12-15-40  
Contractor. R.W.Rine Drlg.Co.  
Issued. 1-18-41

County. Russell



CASING:  
8 5/8" 351' Cem.  
5 1/2" 3321' Cem.

Elevation.

Production. Pot.1113 B.Phy.  
No wtr(flow)

Figures Indicate Bottom of Formations.

surface olay & shells	175
red bed, shale, shells	351
surface & red bed	542
red bed & shale	938
red bed, shale, shells	1038
lime brkn	1055
anhydrite	1147
salt, shale, shells	1334
shale & shells	1548
lime brkn	1650
brkn lime & shale	1750
shale & shells	1862
lime & sand	1964
shale	1978
shale & shells	2128
shale	2230
shale & shells	2437
shale	2537
lime	2561
shale & lime	2604
shale & shells	2738
lime brkn	2833
shale & lime	2965
lime brkn	3035
lime	3321

3321 Rot.T.D.=3322  
Total Depth.

Tops: Lansing 3007  
Arbuckle 3321 Corr.

Loaded hole with wtr & per-  
forated Lansing-Kansas City,  
by Lane-Wells, as follows:  
6 shots 3026-36  
66 shots 3045-67