

CITIES SERVICE OIL CO.
Rogg "D" No. 6

SEC. 9 T. 15 R. 13 W
CEL NE
1320' S. 330' W of NE cor.

Total Depth. 3071
Comm. 11-3-41 Comp. 11-27-41
Shot or Treated.
Contractor. Corbett-Barbour Drilling Co.
Issued. 1-17-42

County Russell.



CASING.

103/4" 338' cemented.
7" 3042' cemented.

Elevation.

Production. Deptho. Pot.
(B.P.) 1432 B. no wtr

Figures Indicate Bottom of Formations.

lime and shale	30
shale sand and iron	100
shale and shells	250
iron	275
shale and shells	450
shale	560
shale and shells	590
red rock and shale	790
anhydrite	850
shale and shells	1015
shale	1064
shale and shells	1225
salt and shale	1312
shale and shells	1505
shale and lime	1631
lime	1676
broken lime	1786
lime	1915
broken lime	1961
lime	2085
broken lime	2160
shale	2233
shale and broken lime	2335
shale and shells	2487
shale and lime	2692
lime	2870
shale and lime	2905
lime	2967
shale and lime	3048
3048 Rot. T.D. equals 3045 SLM	
lime	3071
Total Depth.	

Corr. Top of Lansing 3018
Penetration 53'

FILLUP Loaded hole with 1500' wtr
Hole filled 1500' to 1825' in 1 1/2 hours.
Hole filled 1825' to 1975' in 2 hours.
Hole filled 1975' to 2075' in 2 hours.

5000 gal 11-28-41 12-4-41 5000 gal