


STANOLIND OIL & GAS CO.
R. Roesner No. 5.

SEC. 9 T.15 R.13W
NW NE SE SW
990' N SL 2015' E WL SW $\frac{1}{4}$

Total Depth. 3065'
Comm. 10-18-39 Comp. 12-1-39
Shot or Treated.
Contractor.
Issued. 2-17-40 Cable 3065

County. Russell



CASING:

20" 40'
13" 484.52
7" 3038.54

Elevation.

Production. Pot. 2004 B.
no wtr

Figures Indicate Bottom of Formations.

cellar	10	red rock	2110	Top Tarkio 2404 Sh Oil
shale blue & gy	202	lime brkn	2130	Top Lansing 3027
red rock	225	red rock	2142	
shale gy	255	lime brkn	2156	
red rock	280	lime	2175	
shale blue	300	red rock	2180	
red rock	325	lime	2195	
shale blue	350	shale blue	2225	
red rock	355	lime	2230	
shale blue	370	lime brkn	2250	
sand 3BWPH	385	shale blue	2275	
shale blue & green	415	lime	2285	
sand HFW	430	shale gy & blue	2370	
shale blue	460	lime	2387	
red rock	470	shale dk	2395	
shale blue	485	shale red	2404	
red rock	500	Tarkio - sh oil 2404		
red sand HFW	520	slate blk	2415	
red rock	805	shale blue & lime		
shale blue	820	shells	2450	
lime	824	lime	2462	
anhydrite lime	855	shale blue	2500	
shale blue	860	lime brkn	2515	
red rock	1045	lime	2535	
shale blue	1075	shale blue	2542	
red rock	1125	lime	2547	
shale blue & gy	1250	shale blue	2560	
salt	1505	lime brkn	2570	
shale blue	1510	shale blue	2585	
lime brkn	1525	lime	2595	
shale blue	1535	shale gy	2656	
lime brkn	1565	lime	2680	
shale blue	1570	shale blue	2690	
lime hrd	1575	lime	2695	
lime brkn & shale	1595	shale blue	2700	
lime brkn	1610	lime brkn	2710	
red rock	1615	shale blue	2750	
lime	1635	lime	2805	
lime brkn	1645	lime brkn	2840	
lime gy	1660	lime hrd	2865	
shale blue	1680	lime	2870	
lime gy	1685	shale blue	2880	
lime brkn	1720	lime sh oil 2910-15	2915	
shale blue	1730	lime gy	2935	
red rock	1750	lime hrd	2945	
lime 2BWPH 1760-65	1805	lime	2990	
shale blue & green	1806	shale gy	3005	
lime brkn	1830	shale	3027	
lime gy	1860	lime	3038	
shale blue	1873	shale gy	3041	
lime	1880	shale	3042	
lime brkn & shale	1930	lime	3052	
lime	1950	2BWPH 3048-52		
shale blue	1965	lime porous-cored		
red rock	1970	oil - very sft pay	3056	
lime hrd	1990	lime porous-cored	3065	
shale gy	2000	Total Depth.		
lime	2005			
lime brkn	2015			
red rock	2025	Top Anhydrite 824		
lime brkn	2055	Top Salt 1250		
lime gy	2085			