

STANOLIND OIL & GAS CO.
R. Roesner No. 8.

SEC. 9 T. 15 R. 13W
CN $\frac{1}{2}$ SW SE
990' N SL 660' E WL SE $\frac{1}{2}$

Total Depth. 3342' PB 3155'
Comm. 3-29-40 Comp. 4-27-40
Shot or Treated.
Contractor.
Issued. 6-22-40 Rotary O-3342

County. Russell



CASING:
10 $\frac{3}{4}$ " 630' 7"
7" 3337' 5"

Elevation.

Production. Pot. 1527 B.,
no wtr

Figures Indicate Bottom of Formations.

cellar	8	Core #13 6' 9"/18'	3084
shale & shells	345	rec. 6' 9" hrd lime	
red beds	454	Core #14 0'/3'	3087
shale & shells	578	no recovery, cored 3' lime	
shale	655	lime	3090
shale & red beds	795	shale & lime	3110
anhydrite lime	838	Core #15 8' 6"/18'	3128
shale	940	rec. 3' porous lime w/	
red bed	1087	good sh oil, 15' porous	
shale & shells	1340	lime w/white strks	
salt	1480	Core #16 6' 6"/17'	3145
shale & shells	1564	rec. 6' 6" porous lime	
lime	1655	white	
shale & lime	1838	shale & lime	3278
lime	1992	Core #17 5' 6"/9'	3287
shale & shells	2086	rec. 5' 6" hrd wh lime	
shale	2105	Core #18 9' 11'	3298
shale & lime	2370	shale dk greyish	
shale	2388	blk 3287-3292	
Core #1 10'/10'	2398	lime wh brkn w/red	
rec. 10' blk shale		& green shale part-	
Core #2 3'/10'	2408	ings 3292-95	
rec. 3' blk shale		conglomerate red 3295-98	
shale	2440	Core #19 7' 12' 3298-3310	
lime Tarkio	2444	Core Description:	
shale & lime	2718	shale red	3304
Core #3 9'/18'	2736	lime shaley	3306
rec. 1' lime white		coarse sand-sm sh	
2' 6" gy lime w/some		dead oil	3309 $\frac{1}{2}$
shale		sdv green shale	3310
1' blk shale		Core #20 12'/17'	3327
4' lime w/some shale		Core Description:	
6" gy shale		sand coarse	
Core #4 5' 3"/18'	2754	conglomeratic	
rec. 4' blk shale		& shale 3310-13	
1' 3" lime wh		shale green 3313-14	
shale	2762	dense & non-porous brkn	
lime	2812	weathered dolomite w/	
shale & lime	2888	pyritic green shale	
Core #5 5' 10"/10'	2898	3314-3315	
rec. 1' 4" shale blk, 4' lime		pink & white weathered	
wh, 6" shale w/ lime		dolomite w/green shale	
Core #6 3'/13'	2911	partings, spotted poro-	
rec. 3' lime		sity w/a few small shows	
Core #7 0'/18'	2929	of blk oil 3315-3327	
no recovery, cored 18' shale		Core #21 6'/15' 3327-3342	
shale & lime	3008	lime, no sh of oil 3'	
sh oil 2962-73		cavings	
Core #8 8' 6"/10'	3018	Total Depth	3342
rec. 6' 4" shale blk			
1' 2" shale w/ lime partings			
1' lime gy		No commercial pays en-	
Core #9 4' 3"/10'	3028	countered at total	
rec. 4' lime & 3" shale blk		depth, plugged back to	
Core #10 10'/10'	3038	3155	
rec. 7' shale & 3' lime			
Core #11 5' 3"/10'	3048	Dodge lime 2962-2973	
1' 8" hrd lime & 3' 7" sft		Kansas City lime 3039-66	
porous lime, good sh oil		and 3105-3113	
Core #12 6' 6"/18'	3066	Top Arbuckle 3314	
rec. 1' hrd lime & 5' 6" sft			
porous lime, good sh oil			