

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
J.W. Moharg No. 5


SEC. 17 T. 15 R. 13W.
NW SW NE
990' N and 330' E of the
Center of section.

County Russell.

Total Depth. 3224
Comm. 8-16-39 Comp. 9-11-39
Shot or Treated.
Contractor.
Issued. 10-21-39

CASING.

103/4" 471'
7" 3214'



Elevation.

Production. Pot. 2088 B.

Figures Indicate Bottom of Formations.

surface sand	40
shale and shells	300
sand shale and shells	440
red rock shale	500
shale and shells	560
red rock and shale	670
red rock	750
sdv lime brown	790
red rock and shale	925
red bed and shale	1140
shale and shells	1368
shale and salt	1483
shale and salt	1542
shale and shells	1604
shale and gyp	1663
shale	1726
shale and lime shells	1802
lime	1830
shale	1838
lime	1891
shale	1912
lime	1990
shale and lime	2075
shale and shells	2167
lime and shale	2226
lime	2250
shale and shells	2316
shale	2440
lime	2450
shale	2461
shale	2582
shale and lime	2650
lime	2760
shale blk	2794
shale blk	2831
lime and shale	2860
lime	2980
lime soft	2997
lime	3020
shale	3030
broken lime	3069
lime	3095
lime hard	3140
broken lime	3192
lime	3213
Arbuckle lime	3224
Total Depth.	

Top of Arbuckle lime from cement floor level 3212.
(corrected 1' for derrick floor.)

Total Fill up with oil 2800'

9-15-39 On initial potential test the
well pumped 695.88 bbls of oil in
8 hours giving the well a 24 hour potential
of 2088 bbls of oil no water.

Total depth from cement floor
level 3225 (corrected 1' for
derrick floor)