


CORALENA OIL CO.
Lucinda Sollens No. 9

SEC. 17 T. 15 R. 13W.
SE NE NW

Total Depth. 3200.
Comm. 8-5-39 Comp. 9-2-39
Shot or Treated.
Contractor.
Issued. 10-21-39

County Russell.



CASING.

103/4" 235' 7" 3194'

Elevation.

Production. Pot. 4755 B.
Natural. Echometer.

Figures Indicate Bottom of Formations.

clay sand and shale	285
red rock shale and shells	685
shale and shells	732
anhydrite	775
shale and shells	945
red rock and shale	1180
salt	1380
shale	1450
shale and shells	1580
lime and shale	1705
lime	1790
lime and shale	2210
shale and shells	2425
lime and shale	2660
Top Topeka 2660	
lime	2925
SIM corrected at 2710	
lime and shale	2963
Top Kansas City 2963	
lime	3175
lime and shale	3193
Top Arbuckle 3193	
lime Oil	3200

Total Depth.