


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CORALENA OIL COMPANY.
Holland No. 2

SEC 16 T. 15 R. 13W.
CNL SE NW

Total Depth. 3087
Comm. 6-29-41 Comp. 7-15-41
Shot or Treated.
Contractor.
Issued. 8-9-41

County Russell.



CASING.

103/4" 200' 5 1/8" 3064

Elevation.

Production. Pot. 696 B.

Figures Indicate Bottom of Formations. Physical

no log	156
shale and shells	200
no log	256
shale and shells	835
anhydrite	875
shale and shells	1255
salt	1465
shale and shells	1525
lime and shale	1825
lime	1920
sand	1930
lime and shale	2010
lime	2135
lime and shale	2215
shale	2310
sand	2325
shale	2655
lime and shale	2720
lime	2730
lime and shale	2750
shale	2768
lime	2918
limo Oil stain	2920
limo	2985
limo (Dodge limo)	2990 good sat.
limo	3000
shale	3039
limo hard	3067
limo saturation	3077
limo spotted sat.	3084 1/2
limo	3087

Total Depth.

Top Topeka 2768
Top Kansas City 3039

Completed rotary tools 7-9-41
Commenced cable tools 7-15-41

696 bbls Physical test.
Effective 7-21-41