


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CORALENA OIL CO.
George Sellens No. 6.

SEC. 20 T. 15 R. 13W
CWL NW SE

Total Depth. 3320'
Comm. 10-29-39 Comp. 11-12-39
Shot or Treated.
Contractor.
Issued. 1-6-40

County. Russell



CASING:

10 $\frac{3}{4}$ " 256'
7 " 3316'

Elevation.

Production. Pot. 1772 B.
Echometer

Figures Indicate Bottom of Formations.

no log	256
shale & shells	425
shale, shells, red rock	660
shale & red rock	850
anhydrite & lime	915
shale & red rock	1270
salt	1545
lime, shale, shells	1625
shale & lime	1710
lime	1760
shale & lime	2110
shale	2355
sand & shale	2405
shale	2565
shale & lime	2745
shale	2790
lime	3066
lime, sh oil	3081
lime, sm sh oil	3315
SLM @ 3300	
lime, oil	3320
Total Depth.	

Top Topeka lime 2790
Top Kansas City lime 3051
Top Arbuckle lime 3315