


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

W. I. SOUTHERN, INC.
George Sellens No. 1.

SEC. 20 T. 15 R. 13W
SE SW SW

Total Depth. 3004'
Comm. 10-28-36 Comp. 11-21-36
Shot or Treated. 1000 Gals. & 3000 Gals.
Contractor. Southern & Thurmond
Issued. 12-26-36 Rotary 2992'
Cable 3004'

County. Russell



CASING:

10" 233'9"
7" 3022'9"

Elevation.

Production. Pot. 1063 B.

Figures Indicate Bottom of Formations.

sand & shells	250
shale & shells	510
shale & red bed	790
shale & shells	890
shale & lime	995
shale & shells	1290
shale & salt	1425
shale & shells	1540
shale & lime	1600
shale & shells	1655
shale & lime	1750
shale & shells	1820
lime	1870
lime & shale	1910
lime	2100
lime, shale & shells	2165
lime	2210
lime & shale	2340
shale	2455
lime	2535
shale & lime	2595
lime	2960
shale & lime	2988
lime	2992
Top Oswald	2988'
7" Casing cemented at	2992
Standardized	
lime	3004
Oil from 2999 to 3004	
Hole filled up 800' in 2 hrs.	
Acidized with 1000 gal	
and 3000 Gal.	
Total Depth	3004