


CORALENA OIL COMPANY.
Geo. Sellens No. 1.

SEC 20 T. 15 R. 13W.
SW SE SW

Total Depth. 3065
Comm. 4-21-36 Comp. 6-18-36
Shot or Treated.
Contractor.
Issued. 7-4-36
CASING.

County. Russell.



Elevation.

12 $\frac{1}{2}$ " 487'
10" 834'
8 $\frac{1}{2}$ " 2135'
65/8" 3047'

Production. Pot. 598 B.

Figures Indicate Bottom of Formations.

		line	2050
collar	10	shale	2090
clay	20	red rock	2095
shale	175	line	2100
red rock	135	red rock	2125
shale	260	line	2175
red rock	275	red rock	2200
shale	320	shale	2210
sand 5 BWPH	325	line and shale	2290
red rock	330	shale	2300
shale	360	lime	2305
sand 16 BWPH	365	shale	2335
shale	375	lime	2340
red rock	385	shale	2347
shale	477	lime	2355
sand	485	shale	2375
shale	487	red rock	2380
red rock	832	shale	2400
anhydrite lime	870	red rock	2415
red rock	1045	sdv lime	2420
shale	1080	show oil	
red rock	1135	shale	2455
shale	1220	lime	2470
salt	1505	shale	2530
shale	1525	lime	2540
lime	1530	shale	2570
shale	1540	lime	2610
shale & lime shells	1570	shale	2665
shale	1585	lime	2675
lime	1595	shale	2698
shale	1610	lime	2704
lime	1625	shale	2710
shale	1660	lime	2720
shale lime shells	1670	shale	2740
lime	1680	lime	2747
shale	1700	shale	2758
lime	1730	lime	2815
shale	1760	shale	2820
lime	1775	lime	2837
sdv shale $\frac{1}{2}$ BWPH	1790	shale	2843
shale	1800	lime	2858
lime	1820	shale	2870
shale	1835	lime	2890
lime	1850	shale	2895
sdv lime	1885	lime	2970
shale	1930	shale	2977
lime	1938	lime	3000
shale	1945	red rock	3005
lime	1956	lime	3007
shale	1980	shale	3047
lime	1995	lime	3054
red rock	2000	Top of Oswald S.L.M.	3047
lime	2010	shale	3059
red rock	2035	lime	3065
sand 15WPH	2045	Total Depth.	

Good show oil
Filled up 750' in 40 Min.
Filled up 1150' in 1 hr 40 Min.