

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.  
Redetzke No. 2.

SEC. 21 T. 15 R. 13W  
SW NE NE  
990' S 990' W NE Cor.

Total Depth. 3334' PB 3333'  
Comm. 7-23-40 Comp. 8-9-40  
Shot or Treated. 2000 Gals. 8-11-40  
Contractor. R.W.Rine Drlg.Co.  
Issued. 9-21-40

County. Russell



CASING:  
8 5/8" 322'  
5 1/2" 3326'

Elevation.

Production.Phy.Pot.102 B.  
90% Wtr

Figures Indicate Bottom of Formations.

surface clay & shells	85
shells & clay	322
shale & shells	460
shale & red bed	750
shale & shells	830
anhydrite	870
shale & shells	1060
shale & red bed	1275
shale & salt	1450
shale & shells	1663
lime brkn	2000
lime sdy	2062
lime brkn	2280
shale & shells	2330
shale	2505
lime	2515
shale	2770
lime	3321
rotary TD 3321=3326 SLM	
lime	3326-3334
Total Depth.	

Corr. Top Arbuckle 3324  
Penetration 10

Fillup 350' oil in 8 hrs  
Jetted w/1000 Gals.Acid 8-10-40  
Jetted w/1000 Gals.Acid 8-23-40

Cemented back to 3333'w/15 sacks