


W. I. SOUTHERN, INC.
Sellens Heirs No. 1.

SEC. 29 T. 15 R. 13W
SWc SW

Total Depth. 3275'
Comm. 3-18-36 Comp. 5-4-36
Shot or Treated.
Contractor.
Issued. 9-19-36
CASNG:

County. Russell



10 " 236'
7 " 3027'
5 1/2 " 3271'

Elevation. 1838

Production. Pot. 2003 B.

Figures Indicate Bottom of Formations.

surface & cellar	9
shale & red bed	70
shale & shells	420
shale & red bed	754
red rock, lime anhydrite	835
lime, shale & shells	945
red bed & shale	1050
shale & shells	1250
salt	1435
shale & lime shells	1625
broken lime	1695
lime shells	1760
brkn lime	1855
lime	1980
brkn lime	2045
lime	2190
brkn lime	2265
lime	2325
brkn lime	2440
shale & lime shells	2545
lime & shale	2595
shale & lime shells	2640
lime	2905
brkn lime	3000
shale & lime	3027
lime	3082
Top Oswald	3023
Show oil	3055
shale	3084
lime	3177
shale	3180
lime	3225
shale	3250
lime	3267
conglomerate	3271
lime Siliceous	3275
Total Depth.	

3271
1838
-1433

Show of oil 3107-10