

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

W. I. SOUTHERN, INC.
Sellens Heirs No. 5-C.

SEC.29 T.15 R.13W
CEL NE SE

Total Depth. 3340'
Comm. 6-20-40 Comp. 7-11-40
Shot or Treated.
Contractor. Ruso Drlg.Co.
Issued. 9-14-40

County. Russell



CASING:
8 5/8" 268'
5 1/2" 3335'

Elevation.

Production. Pot.8091 B.Deptho
No wtr

Figures Indicate Bottom of Formations.

clay	25
sand & shale	265
shale & lime shells	510
red bed & shells	750
red bed	850
anhydrite	880
shale & lime shells	1290
salt	1470
shale & lime	1735
shale	1820
shale & lime	1950
lime	2015
shale & lime	2155
shale	2530
shale & lime	2560
shale	2730
shale & lime	2835
lime	3015
shale & lime	3065
lime	3215
shale & lime	3280
lime	3325
shale green	3332
lime	3340
Total Depth.	

Tops: Kansas City-
Lansing 3075
Arbuckle 3335

hole filled 1200' in 5 hrs,
acidized w/1000 Gals.

Coring Record:

- #1 3088-3106 18' rec.
top 9' lime gy, btm 9' sat.
- #2 3163-3183 4' rec.
btm 4' saturated
- #3 3316-3324 5' rec.
grey white lime
- #4 3324-3329 5' rec.
top 6" gy white lime
btm 4'6" green shale
- #5 3329-3331 2' rec.
top 1'6" green shale
btm 6" reworked Arbuckle
- #6 3331-3333 1'9" rec.
reworked Arbuckle
- #7 3333-3335 2' rec.
top 1' reworked Arbuckle
1' shale gy
- #8 3335-3337 2' rec.
Arbuckle lime