


W. I. SOUTHERN, INC.  
Sellens Heirs No. 6B.

SEC. 30 T. 15 R. 13W  
NW SE NW

Total Depth. 3303'  
Comm. 6-23-37 Comp. 7-21-37  
Shot or Treated. 2000 Gals.  
Contractor. Ruso Drlg. Co.  
Issued. 9-4-37 Rotary 3057 Cable 3303

County. Russell



CASING:  
10 $\frac{3}{4}$ " 292'  
7" 3057'  
5 $\frac{1}{2}$ " 3299'

Elevation.

Production. Pot. 2946.16B.

Figures Indicate Bottom of Formations.

shale & sholls	30
sand & shale	305
shale & shells	500
red bed, shale & shells	715
red bed, shale	860
anhydrite	880
shale & shells	1285
salt	1495
shale & lime	1635
shale & lime shells	1700
shale & lime	1950
lime	1980
shale & lime	2045
shale & shells	2115
shale & lime	2305
lime	2360
shale & lime	2520
lime	2570
lime, iron & shale	2610
lime	2650
lime & shale	2770
lime	3005
SIM Corr. 2978 equals 2979	
shale & lime	3045
Oswald lime	3053
Top of Oswald Line	
lime	3065
shale blue	3073
lime	3078
sdv lime	3080
lime	3155
shale blue	3160
lime	3165
lime shells & shale	3195
shale	3197
lime	3233
slate & lime shells	3250
lime	3255
shale	3265
lime & shale	3280
lime	3285
slate	3292
lime Siliceous	3299
lime	3303
Total Depth.	

Top of Siliceous lime 3299