


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CORALENA OIL CO.  
Hank Sellens No. 7

SEC. 30 T. 15 R. 13W.  
NW NE NW

Total Depth. 3317  
Comm. 9-29-37 Comp. 11-3-37  
Shot or Treated.  
Contractor.  
Issued. 12-11-37

County Russell.



CASING.

12 $\frac{1}{2}$ " 504' 8 $\frac{1}{4}$ " 3312'

Elevation.

Production. Pot. 1544 B.

Figures Indicate Bottom of Formations.

sand clay and sholls	350
shalo and sholls	490
sand and water	500
limo and sholls	504
red beds	850
anhydrite	883
shale and sholls	1220
shalo	1260
salt	1460
shale and limo	1725
limo	1775
shale and limo	1860
limo.	2050
shale	2060
limo	2150
shale and limo	2320
shale	2485
shale and limo	2615
shale	2685
limo	2835
Topoka limo	2865
limo	2930
shale	2945
limo	3293
Ran S.L.M. at 3275	
shale	3302
limo	3305
cored 3305-3308 3308-11'	
shale	3309
limo cored 3311-14	3311
limo	3312
Top siliceous limo 3312.	
limo Oil	3317
ran SLM at 3313	
Total Depth.	

Top Oswald 3060 Estimated.