


CORALENA OIL CO.  
Sellens Estate No. 1.

SEC. 29 T. 15 R. 13W  
SW SW SE

Total Depth. 3316'  
Comm. 3-21-37 Comp. 4-11-37  
Shot or Treated.  
Contractor.  
Issued. 5-22-37

County. Russell

CASING:  
12 1/2" 508'  
8 1/4" 3305'  
6 5/8" 30' liner.



Elevation. 1879

Production. Pot. 2566 B.

Figures Indicate Bottom of Formations.

3314  
1879  

---

1435

clay & sand	55
shale & shells	478
sand wtr	494
lime & shells	510
shale	550
red beds & shale	855
anhydrite	890
shale	900
shale & shells	1100
shale & lime	1240
shale	1305
salt	1505
shale & shells	1580
shale & lime	1690
lime & shells	1945
lime	1990
shale & lime shells	2065
lime & shale	2205
shale & shells	2275
lime & shale	2335
shale & shells	2475
shale & lime	2525
lime	2580
lime & shells	2645
shale & lime	2765
shale & shells	2785
Top Topeka	2785
lime	2910
lime & shale	2965
lime	3050
shale & shells	3070
Top Oswald	3070
lime	3110
brkr lime	3170
lime	3230
shale	3270
lime SLM	3310
shale	3314
Siliceous lime Oil	3316
Total Depth.	