

JOHN O. FARMER, INC.

P.O. Box 352
Russell, KS 67665
(785) 483-3144

Distribution:

Presley Petroleum
Terry Marple
Gerald N. Furseth
Paul Simpson
Kirk Rundle
Aven Weaverling
Lance Waymaster
Mike Waymaster

Waymaster #1
840' FSL & 2,390' FWL
Sec. 2 T15S R13W
Russell County, Kansas
1,791 'G.L.
1,799 'K.B.

(N. Trapp 3-D)

Drilling Contractor:

Discovery Drilling - Rig #2
Cell. 785-635-1412
Toolpusher - Dave Dreiling
Geologist - Brad Hutchison
Cell 785-483-0492
Office 785-483-5783

API #15-167-23,562-0000

TIGHT HOLE - DO NOT RELEASE INFORMATION

2/14/2009

MIRU, Spud 12 1/4" @ 6 PM; broke swivel stem while drilling pyrite

2/15/2009

233', drilling;
drill to 415', ran 10 jts new 8 5/8"
(403.53') set @ 413', cemented by Allied w/ 210 sx common
2% gel 3% CC, cement did circulate, completed @ 2 PM.

2/16/2009

950', drilling

2/17/2009

2,119', drilling

2/18/2009

2,795', drilling

2/19/2009

3,180', DST #1

DST #1 3,115-3,180' Lansing H-J

30"-30"-60"-60"

IF: weak blow built to 3.75", no blow back on shut in

FF: weak blow built to 3.25", no blow back on shut in

Rec: 25' SOCM (5% O, 95% M)

60' SWCM (5% W, 95% M)

85' Total Fluid Recovery

FP: 19-39, 43-55#

SIP: 904-904#

HP: 1,541-1,462#

BHT: 98'

2/20/2009

3,350', Plugging

Plugged well as follows:

25 sx @ 3,250'

25 sx @ 760'

80 sx @ 460'

10 sx @ 40'

15 sx in mousehole

30 sx in Rathole

185 sx total-60/40 Poz 4% gel, 1/4# flo-seal/sx,
cemented by Allied, plug down @ 1:30 PM

FINAL REPORT

Louis Mai Operations Lipprand #1 SW NW SW Sec. 2		Estim. from 3D Seismic	JOHN O. FARMER, INC. Waymaster #1 1799			
1858 KB			Sample		E-Log	
Anhydrite	810 1048		744	1055	744	1055
Topeka			2664	-865	2663	-864
Heebner	2965 -1107	-1092	2900	-1101	2899	-1100
Toronto	2980 -1122		2918	-1119	2915	-1116
Brown LS	3040 -1182		2980	-1181	2978	-1179
B/KC	3310 -1452				3237	-1438
Arbuckle	3400 -1542		3281	-1482	3279	-1480
RTD	3450 -1592		3350	-1551		
LTD					3350	-1551