

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


6-15-13W

Company- COOPERATIVE REFG. ASSOC.
Farm- Berrick No. 5

SEC. 6 T. 15 R. 13W
SE SW NE

Total Depth. 3301
Comm. 9-9-51 Comp. 9-20-51
Shot or Treated.
Contractor. Coop. Refg. Assoc.
Issued. 12-8-51

County Russell
KANSAS



CASING:
8" 835' com. w/400 sx
5 1/2" 3291' com. w/125 sx

Elevation. 1843 DF

Production. Pmp. 61 bbls.

Figures Indicate Bottom of Formations.

surface clay	110
shale & shells	420
sand	780
red bed	828
anhydrite	860
red bed, shale & shells	1240
salt	1440
shale & shells	1590
limo	1610
shale & limo	2855
limo	2946
Heebner shale	2951
limo	3270
limo & shale	3291
arbuckle limo	3293
arbuckle limo	3301
Total Depth	

Tops:
Heebner 2944
Toronto 2960
Lansing-Kansas City 3009
Arbuckle 3288