

4-15-13W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.
J. Letsch "B" No. 4-A.

SEC. 4 T. 15 R. 13 W
CSL SW SW
330' N SL 660'E of SWc SW $\frac{1}{4}$

Total Depth. 3347'
Comm. 6-11-43 Comp. 6-28-43
Shot or Treated.
Contractor.
Issued. 10-9-43

County. Russell



CASING:
8 5/8" 551' Cem.
5 1/2" 3326' Cem.

Elevation.

Production. Pot. 853 B.

Figures Indicate Bottom of Formations.

cellar	0-7	Casing was gun perf.w/96 shots from 3056-82
surface sand	100	Tested 3 gals.oily wtr per hr
shale & shells	200	Acidized w/500 Gals.of 15% acid
shale sticky	250	Swbd 76 Bbls load oil & 95 bbls new prod.in 6 Hrs.
pyrite - shale	280	Reacidized w/3500 Gals.of 15% acid & well swbd 34
shale-red bed	380	BOPH, during 3-hr test
pyrite & red bed	420	Pot.853 bbls per day thru 3-inch tubing
red bed	735	
anhydrite	775	Core #1 - cored 3308-11 $\frac{3}{4}$ rec. 3 $\frac{3}{4}$ '
red bed	1275	coring time 3 min.per ft - 60-68-82-88
salt & shale	1450	3308-11 green lime stone brown friable shale
shale	1525	variegated
shale & shells	1585	3311-11 $\frac{3}{4}$ tan to brown lime w/bright green in-
shale & lime	1630	clusions, pyrite & a trace of quartz
lime	1680	grains
shale lime shells	1760	Core #2 - cored 3312-25 rec. 11'
lime & shells	1830	3312-25
lime & shale	1890	top 7' lime & green shale conglomerate
lime hd	1915	next 3' lime, dolomite & green shale
shale	1928	(reworked Arbuckle)
lime	2023	btm 1' dolomite, dense w/a few scattered
shale	2096	slight oil stains
lime & shale	2161	Core #3 - cored 3325-41 rec. 8'
lime	2206	3325-41 all 8' were dolomite w/spotted oil
shale	2468	stains throughout. Some green shale,
lime	2482	bleeding oil very slightly from widely
shale	2508	scattered spots
shale & shells	2611	
shale	2695	
shale & lime	2763	
lime	2967	
shale	2983	
lime	2995	
lime & shale	3054	
lime	3205	
lime & shale	3240	
lime	3283	
lime & shale	3308	
lime	3310	
lime w/shale inclusions	3311 $\frac{3}{4}$	
lime & shale	3314	
lime w/dk brown shale		
partings	3323	
shale	3331	
dolomite	3347	
Total Depth.		

Topeka	2732-2965
Dodge	2968-3027
Lansing	3027-3321
Arbuckle	3324-3347