

PARKER

Form 113 50M 8-49—48374-D

State Kansas County RussellSec. 13 Twp. 15 Rng. 13W Elev. 1826Company Shell OilWell No. 2 Name J. P. (Berriok "A")Location NE SE NEFeet from lines: N. S. E. W. Spud 9-26-49 Completed 12-7-49T. D. 3326 Casing 4" 3325Comp. Perf. SehlPay I. P. D & AChoke T. P. C. P. G. O. R. Grvty.

DATE	REMARKS
12-7-49	Top. 2668, Lans. 2985, Ogl. 3275, Arb. 3305, SSO 3031-38, DST 3027- 41, open 1 1/2 hrs., rec. 30' mud, BHP 900#, SSO 3069-74, DST

DATE

REMARKS

3079-89, open 40 min., rec.
60' O & GCM, & 90' salt wtr.,
BHP 450#.

RTD 3326, Ran Schlum.

CO 3277, 48 § 3030-42,

Swb/1/2 gal. ES & WPH/3 hrs.

4000 A, Swb/2 1/2 WPH/2 hr.

24 § 3066-75, Swb/2 WPH,

scum oil, sqz. perfs.

CO 3277, 48 § 3030-42, tst. 8

GWPH, scum oil, 1000 A,

Swb/2 WPH, 36 § 3066-75,

Sqz. all perfs.

CO 3089, 24 § 3080-86,

tst. 12 GW / SS dead oil per hr.

hr., 36 § 3066-75, 4000 A,

Swb/9 WPH, SS0 per hr., PB

3042, 40 § 3030-42, 2000 A,

Swb/1 WPH/6, PB 2977, 18 §

2935-40, 1000 A, Swb/4 GO /

1 WPH/2, 5000 A, Swb/2 WPH

/ SS0/3 hr., P/3 1/2 BO / 12 WPH/

18 hrs.

D & A

COMPLETE

74769