

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas


35-15-14W

Company - ALADDIN PETRO. CORP.  
Farm - Schneider "B" No. 3

SEC. 35 T. 15 R. 14W  
SW NE NW  
SW NE NW

Total Depth. 3357'  
Comm. 10-15-48 Comp. 10-25-48  
Shot or Treated.  
Contractor. J. D. Ferrell Drlg. Co.  
Issued. 12-18-48

County. Russell  
KANSAS



CASING:

8-5/8" 251' Cem. W/150 Sx. Circ.  
5-1/2" 3355' Cem. W/100 Sx.

Elevation. 1929.2nd  
1917 set  
Production. 150 BOPD

Figures Indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| cellar               | 4    |
| surface lime & shale | 175  |
| scale & shells       | 252  |
| shale, sand & redbed | 605  |
| red bed & shale      | 905  |
| anhydrite & sand     | 935  |
| shale & shells       | 1315 |
| salt & shale         | 1330 |
| salt & shells        | 1580 |
| lime brkn            | 1700 |
| lime & shale         | 2835 |
| lime                 | 2890 |
| lime & shale         | 2925 |
| li e                 | 3045 |
| lime & shale         | 3160 |
| lime                 | 3354 |
| arbuckle lime        | 3357 |
| Total Depth          |      |

Tops: (Rotary Bushing)  
Lansing K. C. 3117  
Arbuckle 3353.3

T.D. Cable Tool Unit 3352 $\frac{1}{2}$  SLM

1' corr. in drill pipe measure.