

2-15-14w


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ALKAY OIL COMPANY
Farm - Bangert No. 3

SEC. 2 T. 15 R. 14 W
SE NW NW

Total Depth. 2993±2991' SIM
Comm. 11-24-45 Comp. 12-6-45
Shot or Treated. 3000 gals. acid
Contractor.
Issued. 2-2-46

County. Russell
KANSAS



CASING:

10 3/4" 448' Cem.
7" 2916' Cem.

Elevation. 1749.2

Production. Pot. 32 BO plus
1% wtr.

Figures Indicate Bottom of Formations.

sand & shale	0-73	lime	2991
shale	250	SIM 2993±2991'	
sand	283	Total Depth.	
shale & shells-pyritic	325		
anhydrite & pyrite	390	Topso	
sand	410	Topoka	2630
red rock & shells	455	Dodge	2874
red rock	750	Kansas City	2916
anhydrite	787		
shale & shells	1160		
salt & shells	1355	Acidized w/3000 gals.	
salt & shale	1375		
shale & shells	1495		
lime	1590		
lime & shale	1735		
lime	1835		
lime sdy & shale	1885		
lime	2040		
lime & shale	2275		
shale	2360		
lime & shale	2425		
lime	2501		
shale & shells	2565		
lime	2575		
lime & shale	2630		
lime gy	2641		
lime sli. sat.	2647		
red rock & shale	2659		
lime sdy, some sat.	2669		
lime & shale	2720		
lime sft	2723		
lime	2728		
lime sdy & shale	2740		
lime & shale	2795		
lime, trace rich sat. in samples	2799		
lime	2804		
lime, sft dolomitic, rich sat.-spotted porosity	2811		
lime & shale	2817		
lime sft, sat.	2841		
lime	2864		
shale	2874		
lime wh spotted sat.	2879		
lime wh	2893		
red rock & shale	2915		
lime gy	2918		
lime sft, oolitic, good sat. & por.	2928		
lime & shale	2939		
lime spotted sat.	2941		
lime	2947		
lime gy oolitic sft, rich sat. porous	2962		