

22-15-14W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company -
Farm - Ochs

THE PHIL-HAN OIL CO. ET AL
No. 3.

SEC. 22 T. 15 R. 14 W
CS $\frac{1}{2}$ NE NE

Total Depth. 3308
Comm. 5-19-45 Comp. 5-31-45
Shot or Treated. Acid 1000 gals.
Contractor.
Issued. 9-22-45

County. Russell
KANSAS



CASING:
8 5/8" 630' Cem.
5 1/2" 3300' Cem.

Elevation. 1859 ft

Production. Pot. 287 B

Figures Indicate Bottom of Formations.

shale	70
shale & sand	375
pyrite & iron	395 ✓
lime sdy	404
shale	480
shale & sand	630
red rock	635
red bed	880
anhydrite	905
lime	910
shale & shells	1370
salt	1485
salt & lime sdy	1630
lime sdy	1655
lime & shale	1815
lime	1890
lime & shale	1893
sand & lime	1950
lime & shale	2045
lime	2080
lime brkn & shale	2181
shale	2295
shale & lime	2400
shale & shells	2600
shale	2625
lime	3020
lime & shale	3090
lime	3144
lime & shale	3148
lime	3219
lime & shale	3233
shale & lime brkn	3256
lime	3308

Total Depth

Top Arbuckle 3298