

23-15-14 W Plotted


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

REPUBLIC NATURAL GAS CO.
Resner No. 3

SEC 23 T. 15 R. 14W.
CE $\frac{1}{2}$ NW SW

Total Depth. 3335
Comm. 6-8-40 Comp. 7-7-40
Shot or Treated.
Contractor. Mitchell Drilling Co.
Issued. 9-28-40

County Russell.



CASING. Rotary 3331
Cable 3335

85/8" 372'
5 1/2" 3329'

Elevation.

Production. Pot. 243 B.

Figures Indicate Bottom of Formations.

surface clay	124
shale and lime	371
shale lime shells	562
shale and shells	880
anhydrite	916
shale and shells	1285
salt	1430
shale and shells	1620
shale	1715
shale and lime	1830
broken lime	1989
lime	2109
broken lime	2290
shale and shells	2545
broken lime	2622
shale and shells	2830
lime	3017
shale and lime	3078
lime	3278
lime and shale	3329
dolomite	3335
Total Depth.	

Tops

Kansas City	3092
Arbuckle	3329

1000 gal acid. 15% Morgan Acid.
4500 gal Acid. 15% Halliburton Acid - Jet.
2000 gal acid. 15% Halliburton Acid