

May 16, 1944

Ohio #1 Stecker
Section 21-15S-14W, C SL SE SW
Elev. 1868'

Rotary Samples

Pennsylvanian Conglomerate: None.

Clean buff-white limestone cover.

Arbuckle Top 3334' Penetration 23'

Subsea -1465'

3329-3331 Cotter. Buff to brown finely crystalline dolomite.
Present in circulation samples at 3331'. Scout
top of Arbuckle at 3334' assumed to be a corrected
measurement.

3331-3334 Cotter. Dolomite, brown and white, coarsely crystal-
line, some oilstaining.

3334-3356 $\frac{1}{2}$ No samples.

Remarks: Test made an initial of 270 bbls. of oil, 48° gravity.

The top of the Pre Cotter cannot be estimated from the short
penetration sampled.

RFW:HL