

30-15-17w ✓

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH


API No. 15 — 051 — 21,050
County Number

S. 30 T. 15 R. 17 W

Loc. SE SE SE

County Ellis

640 Acres
N



Elev.: Gr. 1936'

DF 1938' KB 1941'

Operator

Graham-Michaelis Corp.

Address

211 North Broadway, Box 247 Wichita, Kansas 67201

Well No.

#1-30

Lease Name

Campbell

Footage Location

330 feet from (S) line 330 feet from (E) line

Principal Contractor

Red Tiger Drilling Company

Geologist

George A. McCaleb

Spud Date

March 31, 1975

Total Depth

3525'

P.B.T.D.

Date Completed

April 8, 1975

Oil Purchaser

none

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
To protect fresh water zones	12 1/4"	8 5/8"	24#	1103'	250 sx 60-40 Pozmix	450	2% gel & 2% cc
					200 sx common		2% gel & 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			N O N E		
Size	Setting depth	Packer set at			
N O N E					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD


Amount and kind of material used	Depth interval treated
N O N E	

INITIAL PRODUCTION

DRY & ABANDONED

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
N O N E				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator GRAHAM-MICHAELIS CORPORATION		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1-30	Lease Name CAMPBELL	DRY HOLE	
S <u>30</u> T <u>15S</u> R <u>17</u> ^W (SE SE SE), Ellis County, Kansas			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH
Sod & Sand	0	255'	NO LOG RUN
Shale	255	505	
Sand	505	740	
Sand & Shale	740	834	
Redbed & Shale	1055	1092	
Anhydrite	1092	1140	
Shale	1140	1670	
Shale with Lime	1670	1880	
Shale and Lime	1880	2425	
Shale with Lime	2425	2560	
Shale & Lime	2560	2852	
Lime & Shale	2852	3055	
Shale & Lime	3055	3134	
Lime	3134	3202	
Lime with Shale	3202	3259	
Shale and Lime	3259	3320	
Lime	3320	3375	
Shale & Lime	3375	3450	
Lime	3450	3525 - R.T.D.	
DRILL STEM TEST #1 <u>3288-3320'</u> Open 20", shut in 30", Open 60", shut in 45" Weak blow 25 min. Recovered 30' mud IFP: 54# FFP: 54# IBHP: 87# FBHP: 130#			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received 	<i>Muriel F. C. Jeram</i> Signature Geological Secretary April 18, 1975 Date		