

30-15-17W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- PETROLEUM OPERATING CO.
Farm- Campbell No. 1

S. 30 T. 15 R. 17W
NE NE SE

Total Depth. 3640'
Comm. 6-26-58 Comp. 7-8-58
Shot or Treated.
Contractor. A. L. Jackson Drlg.
Issued. 12-27-58

County Ellis
KANSAS



CASING:
8 5/8" 1140' cem w/250 sx.

Elevation. 1976' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & surface clay	40
shale & chalk	105
water sand	145
blue shale w/lime,	
shells	300
red bed & shale	350
shale & shells	510
sand & shale	550
Dakota-lower zone	780
red bed & blue shale	786
shale	940
red bed	1020
red rock & shale	1080
red bed, shale w/pyrite	1120
& sand streaks.	
red bed, sand & pyrite	1132
Anhydrite	1175
shale & shells	1525
salt & shale	1585
shale, lime & shells	1700
shale	1840
lime	1911
lime & shale	2200
lime, sand & shale	2280
shale & lime	2325
sandy lime, shale,	
strks red bed	2390
shale	2519
shale & lime	3105
lime w/shale breaks	3142
lime	3354
Kansas City lime	3400
lime	3556
Conglomerate	3566
Arbuckle	3640
Total Depth	

Base Kansas City	3514
Sandy Conglomerate	3548
Arbuckle	3584

Ran Schlumberger, Gamma Ray-Laterolog &
Microlaterolog.

DST #1 3540-3556, op 1 hr., weak blow 1 hr.
Rec. 30' oil cut mud, 10% oil, and 130' of
oil & mud. 50-50. 20" ISIP 360#, 20" FBHP
325#. IFP 0#. FFP 70#. This test covered
the Conglomerate Sand.

DST #2 3586-3592, op 30 min., weak 10 min.
blow. Rec. 25' of rotary mud. 20" ICIP
930#. 20" FBHP 905#, IFP 0#, FFP 0#.
This test covered the Arbuckle section.

TOPS:

Anhydrite (Driller)	1132
Topeka	2956
Heebner	3240
Toronto	3259
Lansing-Kansas City	3292