

30-15-17W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RAYMOND OIL CO., INC.
Farm- Leiker No. 1

SEC. 30 T. 15 R. 17W
SW SE SW

Total Depth. 3498'
Comm. 6-16-60 Comp. 6-29-60
Shot or Treated.
Contractor.
Issued. 12-24-60

County Ellis
KANSAS



CASING:

8 5/8" 1076' cem w/450 sx.
5 1/2" 3495' cem w/100 sx.

Elevation. 1918' DF

Production. 6 BOPD

Figures Indicate Bottom of Formations.

sand	80
shale & shells	270
red bed	490
sand	725
red bed w/shale & shells	
pyrite	765 ✓
red bed, shale, sdy lime, pyrite	870 ✓
red rock	925
red bed & pyrite	985 ✓
red bed, shale & shells	1070
red rock	1075
Anhydrite	1106
shale & lime	1775
lime with shale	2165
lime & shale	2395
lime with shale & shells	2410
lime & shale	2505
shale & shells	2603
lime & shale	2645
shale & shells	2760
shale & lime	2950
lime with shale	3000
lime	3160
shale	3169
lime	3180
shale	3187
lime	3210
shale	3218
lime	3225
lime w/trace chert	3265
lime with shale	3400
lime	3449
shale	3462
lime	3465
shale	3470
chert	3486
sand	3490
shale with chert	3493
dolomite	3498 RTD
Total Depth	

TOPS:	
Anhydrite (Driller's)	1075
Heebner	3169
Toronto	3187
Lansing	3218
Base Kansas City	3449
Conglomerate	3470
Conglomerate Sand	3486
Arbuckle	3493