

22-15-18W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP
Farm - Joseph Zimmerman No. 3

SEC. 22 T. 15 R. 18W
NE SW NW

Total Depth. 3629'
Comm. 7-28-48 Comp. 8-23-48
Shot or Treated. Acidized w/100 Gals.
Contractor.
issued. 10-16-48

County. Ellis
KANSAS



Elevation. 2044 Ind.

Production. Oil, 215 Bbl, 86 Wtr.

CASING:

10 3/4" 1199' Cem w/500 Sx. LI
6" 3627' Cem w/125 Sx. LI

Figures Indicate Bottom of Formations.

surface clay 20
shale, shells 375
shale, shells and
redbed 540
sand 545
shale, shells 610
sand 715
shale, redbed 895
shale, shells and
redbed 1040
redbed, shale 1140
redbed, shale and
shells 1190
anhydrite 1240
shale, shells 1640
salt 1795
shale, shells 2075
shale, lime 2195
lime 2260
shale, lime 2335
lime 2435
shale, lime 2995
lime 3545
conglomerate 3629
total depth

Tops:

Heebner 3273'
Toronto 3290
Base/Oread 3310
Lansing 3317
Conglomerate 3588
A buckle 3626

Distance H: Top cellar on
6" is 5' below RB.