


BRIDGEPORT MACHINE CO. ROY H. HALL.
Madden No. 1.SEC 26 T. 15 R. 18W.
NE NW NWDEEPENING RECORD**26-15-18W**

County. Ellis.

Total Depth. 3595'
Comm. 3-31-36 Comp. 6-26-36
Shot or Treated 2000 gal acid.
Contractor. Bridgeport Machine Co.
Issued. 11-21-36

Plotted Texas CO.



NOV 21 1936

CASING.

15 1/2"	384'	8 1/2"	2996
12 1/2"	358'	65/8"	3276'
10"	1275'	53/16"	90' perforated liner

Elevation

Production. Pot. 400 bbls
per day.

Figures Indicate Bottom of Formations.

cellar	15	shale brown	2030	lime	3265
clay yellow	25	lime	2035	lime	3270
shale blue	40	shale blue & shells	2054	lime hard	3281
shale	235	red rock	2060	shale blue & brown	3285
sand 6 BW	240	lime grey	2165	shale blue	3289
shy shale	250	lime	2215	lime	3293
sand	275	red rock	2225	small show oil	
shale grey	290	lime	2235	lime	3302
sand grey	305	broken lime & shale	2260	shale blue	3306
shale blue	335	lime	2295	lime	3312
sand	350	shale blue	2300	shale brown	3315
shale blue	385	red bed	2305	lime	3326
shale	388	lime	2320	lime hard	3331
sand H. F W O	405	shale blue & lime shells	2360	Saturated lime	3341
shale	435	lime	2410	Total Depth.	
shale blue	460	shale blue	2420	Gas and 1750' oil in	
sand lime	468	red rock	2425	20 hours 3331-3541	
lime	470	shale red and blue	2445		
shale blue	490	lime	2495	Well treated with 2000 Gal	
sand	495	shale	2500	acid treated with full	
red rock	505	shale Cave	2505	column of fluid. Displaced	
shale blue	512	lime	2560	thro tubing 50 barrel	
sand	515	shale blue	2565	clearance.	
shale	520	lime	2575		
sand and water	530	shale	2580		
sand brown	550	shale blue	2655		
sand with streaks red		shale	2675		
very sticky	580	lime	2680	Bridgeport Machine Co.	
water sand	594	shale	2695	Old T. D. 3541'	
sand	790	shale blue	2710	Comm. 9-16-36	
red sand rock	815	lime	2713	Comp. 10-31-36	
red rock	835	shale and shells	2720	Pot. Prod. 619 B, No wtr.	
sand	850	lime	2735	Full d 1' r from old T.D.	
red sand rock	858	shale blue	2785	UR 6 5/8" from 3276-3330	
red rock	955	lime	2790	5 3/16" 3540' UR. 3584' 19"	
sand lime	970	shale blue	2805		
red rock	1025	broken lime	2820	Lidiz d 2000 G ls. Acid.	
red sand rock	1145	shale blue and shells	2850		
shale blue & Bentonite	1150	lime	2855	lime	3341-46
lime	1195	broken lime	2875	shale	3347
red rock	1265	lime	2880	lime	3540
shale red	1275	shale blue	2965	red rock	3545
red rock	1340	lime	2970	lime	3560
shale and shells	1370	shale blue	2975	conglom. rat-	3584
shale	1390	shale	2983	Corrected.	
red rock	1435	lime	3010	Arbuckle lime	3590
shale blue	1505	shale	3015	shy lime	3595
shale and shells	1525	lime	3025	Corrected from 3600'	
salt	1745	shale	3030	Total Depth.	
slate	1810	lime 3 BW	3065		
shale blue	1842	lime	3133	500' oil in hole from pay	
broken lime	1870	shale blue	3135	3330-41'	
slate	1880	lime	3175	Hole filled 2000 feet with	
broken lime and blue		lime hard	3180	oil in 24 hours. from pay	
shale	1905	lime shale and shells	3200	3585 to 3595.	
red rock	1920	slight showing gas & oil	3195		
lime	1995	lime hard	3220		
shale blue	2005	lime	3243		
slate brown	2010	shale red & blue	3260		