

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 50S East Murdock, Wichita, Kansas


~~8-15-18W~~  
 8-15-18W

Company. HERMAN GEO. KAISER  
 Farm. Ruder "C" No. 1

SEC. 8 T. 15 R. 18W  
 C S/2 S/2 NE

Total Depth. 3601'  
 Comm. 1-29-61 Comp. 2-11-61  
 Shot or Treated.  
 Contractor. H-30, Inc.  
 Issued. 6-10-61

County Ellis  
 KANSAS



CASING:  
 8 5/8" 212' cem w/150 sx.  
 5 1/2" 3594' cem w/100 sx.  
 DV Tool @ 1188' cem w/450 sx.

Elevation. 2011' DF

Production. 78 BOPD

Figures Indicate Bottom of Formations.

surface soil & post rock	40	
shale & shells	120	
sand streaks	170	
shale & shells	630	
sand	830	
shale & shells	1020	
red bed & shale	1176	
Anhydrite	1220	
shale & shells	1855	
lime & shale	1935	
shale & lime	2090	
lime & shale	2430	
shale & lime	2645	
lime & shale	2920	
shale & lime	3045	
lime & shale	3300	
KC lime	3325	
lime & shale	3347	
lime	3390	
KC lime	3400	
lime & shale	3451	
lime	3490	
KC lime	3550	
lime & shale	3595	
Arbuckle	3601	RTD
Total Depth		

TOPS: SAMPLE

Anhydrite	1176
Base Anhydrite	1220
Heebner	3242
Toronto	3262
Lansing	3286
Base Kansas City	3525
Arbuckle	3591