

8-15-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING
Farm- Ruder "A" No. 5

SEC. 8 T. 15 R. 18W
NW NW SE

Total Depth. 3600'
Comm. 1-6-64 Comp. 1-15-64
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 4-25-64

County Ellis
KANSAS



Elevation. 2011' RB

Production. 40 BOPD

CASING:

8 5/8" 1164' cem w/ 475 sx
5 1/2" 3592.5' cem w/ 125 sx

Figures Indicate Bottom of Formations.

surface clay & rock	75
shale	525
sand & shale	618
sand	825
shale & red rock	915
shale & red bed	1157
anhydrite	1210
shale	1500
shale & lime	3170
lime	3325
lime & shale	3371
lime	3525
lime & shale	3595
Dolomite	3600 RTD
Total Depth	

TCPS: SMP	
Tarkio	2788
Topeka	2962
Heebner	3242
Toronto	3264
Lansing- Kansas City	3289
Arbuckle	3591

DST # 3410-8- Op 70 min. Rec. 40' watery
mud IBHP 832# 30 min; FBHP 387# 30 min.
FP 44#-67#

DST 3580-3600 Op 70 min. Rec. 250' gas,
1650' oil IBHP 1178# 30 min; IFHP 1178#
30 min; FP 99#,-612#