

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

8-15-18W

COMPANY DANE G. HANSEN TRUST

SEC. 8 T. 15 R. 18W

FARM Rohr

NO. 7

LOC. APP 8/2 S/2 NW

TOTAL DEPTH 3586

COMM. 8-15-66

COMP. 8-26-66


SHOT OR TREATED

CONTRACTOR C-G Drllg.

ISSUED 11-19-66

COUNTY Ellis

KANSAS



CASING

20	10		
15	8 5/8"	@ 219.42'	w/150 SX
12	6		
13	4 1/2"	@ 3581'	w/150 SX

ELEVATION 2011' KB

PRODUCTION PMP 25 BOPD, NW
(Arb 3581-84)

FIGURES INDICATE BOTTOM OF FORMATIONS

FROM	TO	FORMATION	VERTICAL	REMARKS
0	219	SHALE & SAND		
219	625	SHALE	3/4°	500'
625	815	SAND	1/2°	1000'
815	1170	RED BED & SHALE	1-1/4°	1400'
1170	1210	ANHYDRITE	1-1/4°	1650'
1210	1835	SHALE & SHELLS	1°	1700'
1835	3310	LIME & SHALE	1°	2000'
3310	3535	LIME	3/4°	2300'
3535	3585	LIME & SHALE	3/4°	2500'
			1-1/4°	3000'
			2°	3570'

DST #1 3285-3310
DST #2 3310-3334
DST #3 3435-3450

TOPS: SCOUT

*Anhydrite	1170
Heebner	3231
Toronto	3253
Lansing	3278
Base Kansas City	3534
Marmaton	3563
Arbuckle	3580

STATE OF KANSAS)
(COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By

[Signature]

W. SWORN TO, BEFORE ME, This 30th day of AUGUST 1966

