

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
 Union National Bk Bldg, Wichita, Kansas.

Plotted Texas CO.

GALVEZ OIL CORP.  
 Carl Ruder No. 1.-A

SEC. 8 T. 15 R. 18W  
 SW • SE

Total Depth. 3322' P.B. 3280'  
 Comm. 1-6-36 Comp. 2-17-36  
 Shot or Treated.  
 Contractor.  
 Issued. 4-18-36

APR 18 1936

County. Ellis

CASING.		Left	In
20 "	66'	66'	
12 1/2 "	810'	810'	
8 1/4 "	3263'	3263'	
6 5/8 "	3270'	3270'	
3" tubing	3319'		



Elevation.

Production. Pot. 1236Bbls.

Figures Indicate Bottom of Formations.

cellar	16
surface clay	30
lime shells & sand	68
shale	125
shale & shells	342
lime shells & shale	466
shale & shells	515
sand brown	600
sand & shale	770
red rock	810
lime	833
shale & shells	1150
lime	1190
shale & shells	1415
shale & boulders	1495
salt	1535
lime	1570
salt	1825
lime hard	1860
broken lime	2065
lime	2350
shale & shells	2400
broken lime	2500
shale & lime	2555
lime	2580
shale & shells	2645
lime hard	2665
shale & shells	2945
lime hard	2985
shale	3010
lime	3050
shale & lime	3105
lime	3280
red rock	3282
1/3 BWPH	
lime Oswald	3297
lime grey soft	3306
Oil from 3297-3306	
lime grey hard	3322

1/4 BWPH 3322  
 Plugged back to 3280' &  
 picked up 6 5/8" pipe to cement  
 Total Depth 3322

Acidized & took potential 1236 Bbls.