

8-15-18W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING
Farm- Swires

No. 4

SEC. 8 T. 15 R. 18W

C EL SW SW SW

Opp. SW NW SW

Total Depth. 3591'

Comm. 6-24-63

Comp. 7-4-63


Shot or Treated.

Contractor. Aylward Drlg.

Issued. 12-7-63

County Ellis

KANSAS



Elevation. 1999' DF

Production. 50 BO / 50 BWPD

CASING:

8 5/8" 1173' cem w/ 475 sx
5 1/2" 3586' cem w/ 125 sx

Figures Indicate Bottom of Formations.

surface clay & shale	425
shale w/ sand streaks	620
sand	825
red bed & shale	905
shale	1165
anhydrite	1215
shale & red rock	1365
shale	1830
shale & lime	2200
lime	2375
lime & shale	2710
shale	2785
shale & lime	2850
shale	3020
lime & shale	3110
lime	3591
Total Depth	

TOPS: LOG

Topeka	2950
Heebner	3233
Toronto	3254(3257)
Lansing- Kansas City	3281(3284)
Arbuckle	3585

DST# 3404-75 Op 70 min. Rec. 55' watery
mud. IBHP 998# 30 min; FBHP 900# 30 min.
FF 52# - 81#

DST 3566-91 Op 70 min. Rec 2400' oil.
IBHP 1021# 30 min; FBHP 983# 30 min;
FF 260#- 790#